WarmlyYours

Environ®

☑ Check List

Materials and Tools Required:

- ☐ Underlayment for carpeting: High quality carpet pad
- ☐ Underlayment for floating engineered wood or laminate: ThermalSheet
- ☐ Customized SmartPlan installation layout
- ☐ A control with built-in GFCI protection and floor temperature sensor
- ☐ Digital ohm meter to test heaters and floor sensor
- ☐ Duct Tape
- ☐ Cardboard or carpet scraps to protect heaters during installation
- ☐ Single gang electrical box for each control
- ☐ Electrical Conduit
- ☐ If multiple heaters are used, they must be wired in parallel to the controller. A junction box is strongly recommended for these installations.

Review Installation & Electrical Plans:

- ☐ Verify available space in circuit breaker box for breakers needed to power the floor
- ☐ Verify dimensions shown on SmartPlan match the install space

Installation:

- ☐ Install underlayment
- ☐ Install floor sensor
- ☐ A licensed electrician to connect the system to the house wiring
- ☐ Install the system in compliance with all local codes

Scan to learn more

Learn More

Videos, Step by Steps, and Project Guides

www.WarmlyYours.com

Installation Support • (800) 875-5285